


Lessons Learned from SRS Salt Processing Scale-Up: Filtration and Solvent Extraction



We Put Science To Work

Michael Poirier

WSRC-STI-2007-00683, Rev. 1

December 4, 2007

Filtration and Solvent Extraction Testing

- **Pilot-Scale Filtration Testing**
- **Rotary Microfilter Development and Testing**
- **Solvent Extraction (MCU) Testing at Vendor**
- **Solvent Extraction (MCU) Testing at SRS prior to Startup**

Pilot-Scale Filtration Testing

- **Constructed pilot-scale filtration unit at the University of South Carolina in 1994-1995**
 - DOE grant to USC
 - Commercial construction firm with USC oversight
 - Full-scale filter tubes
 - 0.625 in ID
 - 10 ft length
 - 7 tubes versus 144 in facility
 - 150 – 500 gallon feed
 - 225 gpm feed pump



Testing Scope and Objectives

- **Completed ~ 30 test campaigns from 1995 – 2003**
 - Tetraphenylborate slurries (1 – 10 wt %)
 - Sludge/MST slurries (0.06 – 12 wt %)
 - Sludge slurries (0.06 – 4.5 wt %)
 - 0.5 and 0.1 m filter media
 - Lasentec particle size analyzer
- **Prepared 600 gallons of simulated sludge for SRS Salt Processing**
- **Cleaned with oxalic acid and nitric acid**

Operation

- **Operated around the clock**
- **Student operators**
 - 4 hour shifts, 2 per shift
- **Limited SRNL presence at test site**
 - Routine data review
 - Hold points established for critical items
 - All corrective actions and recovery paths approved by SRNL
- **Data acquisition system**
- **Analytical laboratory**
 - Particle sizing, IC, GC, AA, Turbidimeter, CEM solids oven
- **SRNL controlled and monitored all test scope**
- **Frequent communications**
- **Data review by SRNL in near “real time”**
- **Bulk of data analysis and reports by SRNL**

Pilot-Scale Filtration Testing Discussion

- **Procedure development**
 - USC personnel drafted procedures
 - SRNL personnel reviewed and approved
- **Laboratory analyses conducted at USC lab**
 - Delays in receiving results due to large number of samples and one chemist
 - Required cross-checking of methods by SRNL and learning curve for USC personnel
- **Equipment problems**
 - Filter leak
- **Test results reviewed by USC and SRNL personnel**
- **Test changes approved by SRNL**
- **Pretest reviews**
 - Formal Readiness Reviews with Lines of Inquiry performed for some tests by cross discipline team (Customer, Operations, SRNL)
 - Independent and periodic QA audits
 - Clean water flux evaluated prior to start of test

Pilot-Scale Filtration Summary

- **What went well**
 - Quantity and quality of data
 - Close location (1.5 hr drive) allowed rapid recovery actions
 - Strong teaming
 - Ran continuously, around the clock
 - USC personnel available around the clock
- **What did not go well**
 - Delay in analytical results
 - Heels and dead legs increased cleaning time and chemicals
 - Difficulty measuring pressure around filter accurately
 - Failed to develop DOE-independent funding for facility leading to higher operating costs
 - Limited staffing led to extended delays for maintenance issues
- **What would you do differently if doing it over**
 - More aggressive effort to establish long term business plans
 - Measure turbidity with meter rather than visually earlier (quantitatively rather than qualitatively)
- **What would you recommend definitely be done in designing, constructing, operating a similar facility**
 - Minimize heels and dead legs in facility to make cleaning easier
 - Broader vision of life cycle and converting to multipurpose testing facility
 - Involvement of other university departments (e.g., for instrumentation, data acquisition, chemical analysis support)

Rotary Microfilter Development and Testing

- 1 – disk commercial unit for feasibility testing at vendor
- 1 – disk commercial unit for actual waste testing at SRS
- 3 – disk commercial unit for pilot-scale reliability testing at USC
- 25 – disk prototype unit (full-scale) for demonstration of enhanced design



Rotary Microfilter Testing Scope and Objectives

- **Conducted feasibility test at vendor site**
 - Evaluate performance on simulated SRS waste
- **Conducted 2 tests with actual waste**
 - Evaluate performance on actual SRS waste
 - Evaluate impact of radiation on unit
- **Conducted 4 tests with pilot-scale unit (> 4,000 hours)**
 - Evaluate reliability of unit
 - Evaluate impact of radiation on filter disks
 - Evaluate alternative filter media
- **Conducted 2 tests with full-scale prototype unit**
 - Enhanced 25 – disk units for deployment
 - Evaluate performance of new equipment design
 - Evaluate remote installation of disk stack
 - Evaluate technology for SRS IX prefilter, SRS sludge washing, Hanford Supplemental Pretreatment

Rotary Microfilter Operation

- **Vendor Feasibility Test**
 - Operated days
 - SRNL approved test procedure
 - SRNL provided feed
 - SRNL representative present for test
 - Manual data collection
 - Vendor report reviewed by SRNL
- **Actual waste test**
 - SRNL Shielded Cells
 - Operated days
 - 1 technician + 1 researcher
 - Manual data collection
- **Pilot-scale**
 - University of South Carolina
 - Around the clock
 - Student operators
 - 2/shift, 4 hour shifts
 - Data acquisition system
 - SRNL reviewed data and wrote report
 - SRNL
 - Operated days
 - 2 personnel
 - Manual data collection
- **Full-scale Prototype**
 - 2 technicians + 1 researcher
 - Operated days
 - Manual data collection

Rotary Microfilter Discussion

- **Procedure development**
 - USC prepared procedures – SRNL reviewed and approved
 - SRNL prepared procedures
- **Laboratory analyses limited to turbidity**
 - Conducted at site
- **Equipment problems**
 - None during actual waste and full-scale tests
 - Rotor plugged during pilot-scale test – due to concentrated manganese feed slurry
 - Rotary union failure – due to manufacturer using wrong material
 - Ceramic membrane tore – final selection was SS membrane
 - Interlocks shutting system down due to low tank level, elevated temperature, and low feed pressure
- **Test results reviewed by SRNL, LWO, and DOE-SR**
- **Pretest reviews**
 - Readiness Review (with formal lines of inquiry) performed before some tests
 - Clean water flux evaluated prior to start of test

Rotary Microfilter Summary

- **What went well**
 - No problems with mechanical seal
 - Thorough review of prior test history and related designs (SRS, LANL, INEEL, DuPont, ASPECT)
 - Developed Intellectual Property working relationship with vendor and long term vision early
- **What did not go well**
 - Limited review of vendor electronics
 - Overaggressive procurement of 2 prototype units
 - Did not obtain end user commitment and project design owner early as desired
- **What would you do differently if doing it over**
 - Data acquisition system would improve quantity and quality of data
 - Incorporate more advanced vibration, wear, and heat measurements earlier
 - Order broader set of membranes for testing (instead of 2 units)
 - Expand effort to understand flow distribution in equipment
 - Pursue a commercial end user in parallel more aggressively
 - Earlier independent review of seal materials and options
- **What would you recommend definitely be done in designing, constructing, operating a similar facility**
 - Upgrade supply pump rather than use “best available”
 - Add automated data acquisition
 - Obtain operations engineer overview and involvement (attempted but unable to raise user interest high enough)
 - Upgrade system electronics

Solvent Extraction (MCU) Testing at Vendor

- **Contract awarded for testing to Wright Industries (WII)**
- **3 months from award of contract to start of testing**
- **Testing conducted over 16 months**
- **Scope increased as a result of testing (as expected)**
- **Cost ~ \$5 – 6 million**

Solvent Extraction Vendor Test Work Completed

- **Individual V-10 & V-05 Testing**
 - Hydraulics
 - Air Flow
 - Mass Transfer
 - Solvent Carry Over
- **Decanter Testing**
 - Solvent Carryover
 - Solvent Droplet Distribution Generated by Mix/Shear Pump
 - Pump Required for Coalescer Pressure Drop
- **Integrated Testing**
 - Durability Testing
 - Mass Transfer
 - Solvent Carryover
- **Significant modification resulted from work completed**

Solvent Extraction Vendor Test Operation

- Operation included around the clock and day only
- SRS-LWO personnel at test site
- PLC control and data acquisition system
- Offsite analytical lab
- Personnel
 - 1 operator
 - 1 SRS representative
 - 1 test engineer
 - 2 maintenance personnel available

Solvent Extraction Vendor Testing Summary

- **What went well**
 - Contactors/coalescers met performance requirements
 - Testing met aggressive schedule
 - Transfer of sample handling protocol to commercial lab
- **What did not go well**
 - Material compatibility - contamination of solvent from DEHP in plastic tubing
 - Vendor measured vibration by acceleration rather than vibration amplitude
 - Transfer of organic sample digestion protocol to commercial lab
 - Pressure drop across the coalescer higher than expected
 - May have been early indication of sodium aluminosilicate
- **What would you do differently if doing it over**
 - Select vendor with more expertise in process engineering
- **What would you recommend definitely be done in designing, constructing, operating a similar facility**
 - Ensure vendor control system is aligned with SRS/MCU control system

SRS Solvent Extraction (MCU) Testing Prior to Startup

- **Moved unit from WII to SRS**
- **Installed and conducted mass transfer tests with simulant**
- **Full-scale**
- **Conducted tests to confirm unit performance following installation**

SRS Solvent Extraction Testing Issues

- **Sodium Aluminosilicate (NAS) Precipitation**
 - Resulted in coalescer media pluggage
 - Required filtration unit installation
 - May have occurred during WII testing
 - Could have tested in advance
 - Did not control vendor sufficiently
- **Iron Contamination in Scrub Feed Tank**
 - Provided sodium aluminosilicate precipitation site
 - Existing tank re-used and not thoroughly cleaned
- **Emulsion**
 - Formed In wash contactors
 - Solvent density out of specification
 - Solvent density monitored with bubbler – went off scale – could have collected additional samples

SRS Solvent Extraction Testing Operation

- **Around the clock**
- **2 operators in control room**
- **2 operators in field**
- **1 engineer**
- **Samples sent to SRNL for analysis**

SRS Solvent Extraction (MCU) Testing Summary

- **What went well**
 - Process performed as expected
 - Preplanning between MCU, SRNL, and Analytical personnel allowed rapid completion of sample analyses
 - Teaming between MCU and SRNL allowed rapid resolution of operational issues
- **What did not go well**
 - Sodium aluminosilicate precipitate formed
 - Scrub feed tank contained iron contaminant
 - Emulsion formed due to Isopar[®] L evaporation
- **What would you do differently if doing it over**
 - When density measurement went off scale, collect additional samples
 - Ensure all tanks are clean
 - Re-use of existing equipment requires thoroughly documented inspections/testing – expect the unexpected
- **What would you recommend definitely be done in designing, constructing, operating a similar facility**
 - Consider Process Upsets for Instrumentation Design
 - Ensure adequate instrumentation in facility