
# Savannah River Site Waste Disposition Project



Terrel J. Spears
Assistant Manager
Waste Disposition Project
DOE Savannah River Operations Office



### Waste Disposition Project - Mission

# Radioactive Liquid Waste - Tank Waste Stabilization and Disposition

- Disposition 36 million gallons of radioactive liquid waste
- Close 49 underground storage tanks in which the waste now resides








## Liquid Waste Background

### Facts...


- 2 tanks closed
- 49 tanks remaining to close
  - aging, carbon steel
  - 27 compliant, 22 non-compliant
  - 12 have known leak sites
- Contain half of the radioactivity in the DOE complex
- 1.3 million gallons remaining usable space







### **Tank Space**







**Note:** Usable space = Available compliant tank space less processing space and contingency space

# Radioactive Liquid Waste Disposition

"Radioactive waste stored in SRS tanks poses the single greatest environmental risk in the State of South Carolina."

### **Challenge:**

- Safely store, treat and stabilize legacy liquid waste
- Remove waste and close 49 remaining waste tanks

### Regulatory Framework


- Federal Facility Agreement (FFA) Close all non-compliant tanks by Fiscal Year (FY) 2022
- Site Treatment Plan (STP) remove waste from all tanks by FY 2028
- Tank Closure and waste disposition must meet Section 3116(a) of the Ronald W. Reagan National Defense Authorization Act for FY 2005
- Facilities operated under State-issued permits
- Total radioactivity sent to Saltstone vaults limited to 1.4M Curies








## **Liquid Waste Processing Today**



## **Liquid Waste Processing Tomorrow**



### DDA

### Deliquification, Dissolution, and Adjustment (DDA)



- Remove free supernate
- Drain interstitial liquid
- Store for future processing at Salt Waste Processing Facility
- Dissolve saltcake and transfer of salt solution
- Allow solids to settle
- Transfer to Saltstone feed tank
- Aggregate with other Tank Farm waste to meet processing parameters (if required)





- Initiated processing in 3/2007
- Demonstration batches complete
- Currently processing Tank 41 waste



### **Actinide Removal Process**

#### **Objective:**

Provide near term capability to remove actinides and strontium (Sr-90) from salt waste at a rate of 1.2 million gallons per year

### Scope:

- Process to be conducted in two existing modified site facilities (241-96H and 512-S)
- Involves introduction of mono-sodium titanate (MST) into the strike tanks in 241-96H filled with salt solution from Tank 49 followed by filtration of adsorbed actinides and Sr-90

- Completed integrated runs 11/07
- Operational readiness review complete
- Hot startup in progress





### MCU

#### **Objectives:**

- Remove Cesium (Cs-137) from clarified salt waste received from the ARP
- Develop operating experience on a largescale CSSX process to optimize the startup and initial operations of SWPF


#### Scope:

- MCU uses the same technology and similar equipment as the SWPF
- MCU will provide Cs-137 removal capability (decontamination factor of ~100) from about 1.2 million gallons of salt waste per year

- Completed integrated runs 11/07
- Operational readiness complete
- Hot startup in progress







### Tank 48 Recovery

**Objectives:** 

Treat 240,000 gallons of highly radioactive liquid waste that also contains

about 21,800 kg of organic compounds
Return 1.3 million gallons of vital tank space to Tank Farm service


Scope:

Tank 48 Treatment Process will provide the capability to treat salt waste and destroy the organics
Tank 48 will serve as feed tank for SWPF

- Critical Decision (CD) 1 approved 3/08
- Project completion targeted for 2012 to support SWPF startup







### **SWPF**

#### **Objective:**

Rapidly and efficiently treat salt waste stored in SRS tank farms to remove actinides, Sr-90 and Cs-137

#### Scope:

- Remove and concentrate Cs-137 and Sr-90/actinides from salt waste and send them to DWPF
- Send decontaminated stream to Saltstone
- Nominal capacity of SWPF ~6.0 Mgal/yr
- Total volume to be processed ~85 Mgal
- Approved TPC \$899M
- Completion date (80% confidence level) November 2013

- Baseline and initial procurement/construction approved 9/24/07
- Construction underway







### **DWPF Vitrification**

#### **Objective:**

Process (vitrify) HLW from SRS tank farms into a stable waste form ready for disposal in the Federal Repository


### Scope:

- Design started in 1977
- Construction began 1983
- Radioactive operations began March 1996
- Sludge feed currently being processed from old style tanks to meet regulatory commitments

- Poured over 2,480 canisters to date
- Continuing to optimize process performance







### **Saltstone Facility**

#### **Objective:**

Process low activity salt stream into grout for disposition in vaults

### Scope:

- Aqueous waste mixed with flyash, slag and cement
- Poured in concrete vaults to solidify
- Engineered disposal facility
- Low water permeability
- Excellent non-leaching qualities
- Non-hazardous product


- Modifications completed 10/07
- Currently processing DDA waste
- Continuing to enhance process







## Liquid Waste Project Schedule



# **Current Challenges - Storage**

### Safely operating aging SRS Tank Farms

- Decaying infrastructure and forced outages
- Strategy: Use system health analysis to identify vulnerabilities and restore selected infrastructure spares via small projects

### Creating sufficient space to support SWPF

- Successful execution of interim processing essential
- Preparing qualified feed consumes space in the near term due to salt dissolution and sodium adjustment
- Strategy: Recover Tank 48 and optimize existing infrastructure to recover Tank 50 to high level waste service





# **Current Challenges - Retrieval**

- Federal Facilities Agreement
  - Technology uncertainties and Section 3116 process create risk to 2022 completion date for closure of non-compliant tanks
  - Strategy: Develop and deploy new tank cleaning technologies to accelerate preparation of tanks for closure
  - Strategy: Limit Waste Determination submittals to one per Tank Farm





# **Current Challenges - Treatment**

### Site Treatment Plan

- Current estimates of sludge mass and salt processing capability create risk to 2028 date for completion of waste removal and treatment
- Strategy: Timely start of SWPF
- Strategy: Implementation of sludge mass reduction technologies
- Strategy: Employ new melter technologies to increase waste loading and throughput
- Strategy: Potentially augment salt processing through alternative treatment technologies
  - Evaluate small column ion exchange
  - Improve effectiveness of ARP/MCU and operate longer





## Current Challenges – Tank Closure

- SR inexperience with public review of performance assessments (PA)
  - HQ support needed to educate stakeholders
- Limited data available to support waste removal to maximum extent practical
- Improved physical property data needed to support waste removal and PA's





### **Technology - Ongoing Site Initiatives**

### Tank 48 Recovery Project

- Fluidized Bed Steam Reforming
- Wet Air Oxidation (risk mitigation)

### Sludge Mass Reduction

Low temperature leaching in Tank 51 reduced aluminum in Sludge Batch 5

### Sludge Waste Processing

Increased Waste loading in glass and increased melt rate

### Sludge Heel Removal

- Mechanical Cleaning in Tanks 18, 19
- Chemical Cleaning in Tanks 5, 6







### **Technology - Needs**

#### Waste processing

- Increased glass waste loading and melt rate
- Accelerated sludge batch preparation
- Vitrification rate increase by melter technologies

#### Augment salt processing

- Small Column Ion Exchange
- ARP/MCU enhancements and life extension.

#### Sludge Heel Removal


 Develop and deploy Enhanced Chemical Cleaning, to reduce downstream oxalic acid impacts at DWPF

#### Closure

 Develop physical property data to support PA's for tank farms and Saltstone, including improved tank closure grouts







**Shielded Cells Testing with Actual Waste** 



### Issues

### Technical

- Scarce expert resources to perform performance assessments
- Develop physical property data to support PA's for tank farms and Saltstone, including improved tank closure grouts

### Regulatory

 A revision process for the WD is needed to allow deployment of new technologies not included in the current WD





# Summary

- Liquid waste processing strategy in place
  - Sludge and interim salt treatment underway
  - SWPF under construction
- Many challenges remain
  - Tank 48 and 50 recovery
  - Sludge mass reduction
  - Enhanced DWPF throughput
  - Augmentation of existing salt processing
- Ongoing collaborations and investment in new technology are essential to success



